REPOSTING OF THE PROCUREMENT OF REPAIR AND MAINTENANCE OF VARIOUS TUPC BUILDINGS

Solicitation Number:	TUPC-26-046
Trade Agreement:	Implementing Rules and Regulations
Procurement Mode:	Negotiated Procurement - Small Value Procurement (Sec. 34)
Classification:	CIVIL WORKS
Category:	Construction Projects
Approved Budget for the Contract:	PHP 400,000.00
Delivery Period:	60 Day/s

Contact Person:

Ramon Christopher H Escalona
Buyer III
C.Q.T. Ave., Salawag,
Dasmariñas City
Cavite
Philippines 4114
63-46-4164920
63-46-4162122
tupc.procurement@tup.edu.ph

Description

THE TECHNOLOGICAL UNIVERSITY OF THE PHILIPPINES CAVITE
Bids and Award Committee

Invitation to prequalify & request for quotation notice is hereby given that the TUPC will conduct a small value procurement by way of a sealed quotation for the REPOSTING OF THE PROCUREMENT OF REPAIR AND MAINTENANCE OF VARIOUS TUPC BUILDINGS

The Following schedule of the SMALL VALUE PROCUREMENT process shall be observed:

- The interested parties must submit eligibility requirements and GEPS certificates of registration on or before November 16, 2026, 8:00 AM through email:

⎫ tupc.procurement@tup.edu.ph / Cc: tupc_bacsec@tup.edu.ph

- All quotations must be submitted on or before November 16, 2026, 8:00 AM through email:
⎫ tupc.procurement@tup.edu.ph / Cc: tupc_bacsec@tup.edu.ph

- TUP Cavite campus reserves the right to reject any or all quotations, to decide the bidding/shopping of failure or waive any or all information, or to award such bids to the supplier/bidders whose bids are considered most advantageous to the Government, and makes no assurance that a contract shall be entered into as a result of this invitation.

TUPC reserves the right to reject any bids, waive any contained therein, and accept the most advantageous to the Philippine Government.

Approved Budget of Contract:₱ 400,000.00

Interested parties may send their queries and concerns through tupc.procurement@tup.edu.ph and cc: tupc_bacsec@tup.edu.ph or you may call (046) 416-4920 loc. 401 and look for Engr. Ramon Christopher H. Escalona.

Dr. Emily L. Beltran
BAC Chairperson

Other Information

See attached PROGRAM OF WORKS

SITE INSPECTION IS REQUIRED, coordinated with the TUP-Cavite Infrastructure Development Office (IDO)

TECHNOLOGICAL UNIVERSITY OF THE PHILIPPINES
CAVITE CAMPUS
Carlos Q. Trinidad Ave., Salawag, Dasmariñas City, Cavite

PROGRAM OF WORKS FOR THE PROPOSED VARIOUS REPAIR OF ROOFING

SCOPE OF WORKS

I. **REPAIR OF TUPC LIBRARY ROOFING**

The work consists of the supply and installation of pre-painted GI sheet roof flashing, including measurement, cutting, forming, positioning, fastening, application of sealant, installation of aluminum tape, and final inspection.

DESCRIPTION	QTY	UNIT	UNIT PRICE	AMOUNT
Pre-painted GI Sheet, Red, 0.60 mm, 4' x 8'	41	sheet	/sheet	-
Concrete Nails, 1"	3	kg	/kg	-
Construction/Roof Sealant, 300 ml	35	tube	/tube	-
Aluminum Tape	120	lm	/lm	-
Scaffolding -erection, rental, shifting and dismantling	1	lot	/lot	-

MATERIAL COST	P	-
LABOR COST	P	-
DIRECT COST	P	-

II. REPAIR OF NEW ACADEMIC BUILDING ROOFING

The work consists of the supply and installation of pre-painted GI sheet roof flashing, including measurement, cutting, forming, positioning, fastening, application of sealant, installation of aluminum tape, and final inspection.

DESCRIPTION	QTY	UNIT	UNIT PRICE	AMOUNT
Pre-painted GI Sheet, Red, 0.60 mm, 4' × 8'	45	sheet	/sheet	-
Concrete Nails, 1"	3	kg	/kg	-
Construction/Roof Sealant, 300 ml	40	tube	/tube	-
Aluminum Tape	90	lm	/lm	-
Scaffolding -erection, rental, shifting and dismantling	1	lot	/lot	-

MATERIAL COST	P	-
LABOR COST	P	-
DIRECT COST	P	-

III. MISCELLANEOUS

MATERIALS:

DESCRIPTION	QTY	UNIT	UNIT PRICE	AMOUNT
Mobilization	1	lot	/lot	-

DIRECT COST	P	-

TOTAL DIRECT COST	P	-
OVERHEAD/CONTIGENCY/MISC		-
CONTRACTOR'S PROFIT		-
EVAT (12%)		-
TOTAL ESTIMATED PROJECT COST	P	-

PREPARED BY:

[redacted]

Engr. Brylle Ephraiem Q. Navarro
IDO-Chairperson

APPROVED BY:

[redacted]

Engr. Alexander E. Mag-Isa, Ph.D., PME
Campus Director